HASSAN DIVISION.

Dated 18th December 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 18th January 1931, till 2 P.M., for sinking a draw well and constructing compound wall to the Maternity Hospital at Saklespur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes, as earnest money and be superscribed "Tender for sinking a draw well and constructing compound wall to the Maternity Hospital at Saklespur" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates should be written both in figures and words.

Abstract estimate for sinking a draw well and constructing compound wall to the Maternity Hospital at Saklespur.

No.	Items of work	Unit	Rate	Quantity	Cost
	Sinking a well.		Rs. a. p.		
1	Earthwork excavating, 1st fathom ...	C.yd.		39	
	Do 2nd do ...	,,		37	
	Do 3rd do ...	,,		34	
	Do 4th do ...	,,		29	
	Do 5th do ...	,,		28	
	Do 6th do ...	,,		25	
	Do 7th do ...	,,		21	
	Do 8th do ...	,,		19	
	Do 9th do ...	,,		18	
	Do 10th do ...	,,		14	
	Do 11th do ...	,,		13	
	Do 12th do ...	,,		11	
2	Constructing burnt stone steining wall dry ...	,,		100	
3	Jelly back to steining wall of the well ...	,,		188	
4	Burnt brick in mortar ...	C.ft.		89	
5	Burnt stone slabs 6" thick dressed and fixed ...	S.ft.		242	
6	Surki mortar plastering ...	Sqr.		1·10	
7	Matti wood cross beam including fixing ...	C.ft.		4·00	
8	Pointing with surki mortar (from 72' depth) ...	Sqr.		9·05	
9	Constructing a lead off drain, baling water during execution, etc.	Lump sum			
10	Providing an iron pulley including fixing, etc., complete.	No.		1	
11	Cutting grooves in the vertical slabs for the cross beam.	,,		2	
	Compound Wall.				
1	Earthwork excavating foundation ...	C.yd.		15	
2	Burnt brick in clay ...	C.ft.		423	
3	Plastering with chunam mortar ...	Sqr.		7·52	
4	Coping with burnt brick in mortar and chunam plastering, etc., complete.	R.ft.		60	

M. A. SRINIVASACHARI,